


## **APPENDIX D**



## **APPENDIX D – EXHIBIT 1**

```

*****
*           AMAX DATA SYSTEMS           *
*   ENGINEERING SYSTEMS DEVELOPMENT     *
*           ENVIRONMENTAL ENGINEERING    *
*           HYDROGRAPH GENERATION        *
*****

```

HYGEN - Version 3.2I  
 FILE: BASINSP3 PRREPORT A

JANUARY 26, 1990

PROJ TITLE: PROPOSED SEDIMENT BASIN SP-3  
 SILTATION CONTROL FOR PLANT AREA

LOCATION: AMAX COAL INDUSTRIES INC - PENNDIANA FLD  
 SULLIVAN COUNTY, INDIANA

WATERSHED: DISTURBED AREA AROUND PREP PLANT

#### WATERSHED ANALYSIS TABLE

##### METHOD OF COMPUTATION

RUNOFF VOLUME	= Bureau of Reclamation
PEAK DISCHARGE	= SCS Unit Hydrograph

##### RAINFALL PARAMETERS

RAINFALL RETURN PERIOD	= 10.0 YEARS
RAINFALL DURATION	= 24.00 HOURS
RAINFALL AMOUNT	= 4.51 INCHES
TIME INTERVAL	= 0.10 HOURS
RAINFALL DISTRIBUTION	= SCS Type II

##### WATERSHED PARAMETERS

TOTAL WATERSHED AREA	= 32.3 ACRES ( 0.050 SQ MI)
SCS RUNOFF CURVE NUMBER	= 87.0
MINIMUM RETENTION RATE	= 0.065 INCHES/HOUR
TIME OF CONCENTRATION	= 0.56 HOURS

##### RAINFALL - RUNOFF SUMMARY

PEAK DISCHARGE	= 74.2 CFS
TIME TO PEAK (FROM START OF RAIN)	= 12.3 HOURS
RUNOFF VOLUME	= 6.8 ACRE-Feet

```

*****
*           AMAX DATA SYSTEMS           *
*   ENGINEERING SYSTEMS DEVELOPMENT     *
*           ENVIRONMENTAL ENGINEERING    *
*           RESERVOIR ROUTING            *
*****

```

RSROUT - Version 2.01  
 FILE: BASINSP3 PRREPORT A

JANUARY 26, 1990

PROJ TITLE: PROPOSED SEDIMENT BASIN SP-3  
 SILTATION CONTROL FOR PLANT AREA  
 LOCATION: AMAX COAL INDUSTRIES INC - PENNDIANA FLD  
 SULLIVAN COUNTY, INDIANA  
 RESERVOIR: SEDIMENT BASIN SP-3  
 PLANT AREA SEDIMENT CONTROL

### RESERVOIR ROUTING - SUMMARY TABLE

(ALL TIMES ARE FROM START OF RAINFALL)

#### INFLOW PARAMETERS

WATERSHED AREA-----:	32.30 ACRES
RAINFALL RETURN PERIOD-----:	10.00 YEARS
RAINFALL DURATION-----:	24.00 HOURS
RAINFALL AMOUNT-----:	4.51 INCHES
TIME AT START OF INFLOW-----:	6.20 HOURS
PEAK INFLOW-----:	74.19 CFS
TIME TO PEAK INFLOW-----:	12.30 HOURS
INFLOW RUNOFF VOLUME-----:	6.76 ACRE-Feet
TIME TO END OF INFLOW-----:	20.30 HOURS

#### RESERVOIR PARAMETERS

RESERVOIR ELEV. AT START OF STORM--:	550.00 FEET
NORMAL POOL ELEVATION-----:	550.00 FEET
EMBANKMENT CREST ELEVATION-----:	555.00 FEET

#### STORAGE VOLUME & DISCHARGE RATE AT:

POOL ELEVATION AT STORM START:	10.49 AC-FT,	0.0 CFS
NORMAL POOL ELEVATION-----:	10.49 AC-FT,	0.0 CFS
EMBANKMENT CREST ELEVATION-----:	19.89 AC-FT,	1747.3 CFS

#### ROUTING SUMMARY

PEAK RESERVOIR ELEVATION-----:	550.90 FEET
TIME TO PEAK RESERVOIR ELEVATION--:	12.50 HOURS
OUTFLOW RATE AT PEAK ELEVATION-----:	62.10 CFS
FREEBOARD AT PEAK ELEVATION-----:	4.10 FEET
* TIME TO DRAWDOWN TO NORMAL POOL--:	7.90 HOURS
OUTFLOW RUNOFF VOLUME-----:	6.79 ACRE-Feet
ROUTING TIME INCREMENT-----:	0.10 HOURS

\* NOTE: FROM TIME OF PEAK RESERVOIR ELEVATION

RSROUT - Version 2.01  
FILE: BASINSP3 STORAGE

JANUARY 26, 1990

PROJ TITLE: PROPOSED SEDIMENT BASIN SP-3  
SILTATION CONTROL FOR PLANT AREA  
LOCATION: AMAX COAL INDUSTRIES INC - PENNDIANA FLD  
SULLIVAN COUNTY, INDIANA  
RESERVOIR: SEDIMENT BASIN SP-3  
PLANT AREA SEDIMENT CONTROL

RESERVOIR ELEVATION VS SURFACE AREA AND STORAGE

---

RESERVOIR ELEVATION	SURFACE AREA	STORAGE CAPACITY
(FEET)	(ACRES)	(AC-FT)
540.00	0.00	0.00
542.00	0.73	0.73
545.00	1.16	3.57
550.00	1.61	10.49
555.00	2.15	19.89

RSROUT - Version 2.01  
FILE: BASINSP3 DISCHRG A4

JANUARY 26, 1990

PROJ TITLE: PROPOSED SEDIMENT BASIN SP-3  
SILTATION CONTROL FOR PLANT AREA  
LOCATION: AMAX COAL INDUSTRIES INC - PENNDIANA FLD  
SULLIVAN COUNTY, INDIANA  
RESERVOIR: SEDIMENT BASIN SP-3  
PLANT AREA SEDIMENT CONTROL

OUTLET DEVICE: OPEN CHANNEL SPILLWAY - 10 FT BOTTOM

RESERVOIR ELEVATION VS. DISCHARGEFIRST OUTLET DEVICE

<u>RESERVOIR ELEVATION (FT)</u>	<u>DISCHARGE (CFS)</u>
550.00	0.00
550.10	1.50
550.20	4.70
550.30	9.30
550.40	15.20
550.50	22.20
550.60	30.50
550.70	39.90
550.80	50.40
550.90	62.10
551.00	62.10
551.20	104.20
551.40	138.30
551.60	177.20
551.80	221.30
552.00	270.50
553.00	600.90
554.00	1086.50
555.00	1747.30

```

*****
*           AMAX DATA SYSTEMS           *
*   ENGINEERING SYSTEMS DEVELOPMENT     *
*   ENVIRONMENTAL ENGINEERING           *
*   HYDROGRAPH GENERATION               *
*****

```

HYGEN - Version 3.2I  
 FILE: BASINSP3 PRREPORT A

JANUARY 26, 1990

PROJ TITLE: PROPOSED SEDIMENT BASIN SP-3  
 SILTATION CONTROL FOR PLANT AREA

LOCATION: AMAX COAL INDUSTRIES INC -- PENNDIANA FLD  
 SULLIVAN COUNTY, INDIANA

WATERSHED: DISTURBED AREA AROUND PREP PLANT

### WATERSHED ANALYSIS TABLE

#### METHOD OF COMPUTATION

RUNOFF VOLUME  
 PEAK DISCHARGE

= Bureau of Reclamation  
 = SCS Unit Hydrograph

#### RAINFALL PARAMETERS

RAINFALL RETURN PERIOD  
 RAINFALL DURATION  
 RAINFALL AMOUNT  
 TIME INTERVAL  
 RAINFALL DISTRIBUTION

= 25.0 YEARS  
 = 24.00 HOURS  
 = 5.12 INCHES  
 = 0.10 HOURS  
 = SCS Type II

#### WATERSHED PARAMETERS

TOTAL WATERSHED AREA  
 SCS RUNOFF CURVE NUMBER  
 MINIMUM RETENTION RATE  
 TIME OF CONCENTRATION

= 32.3 ACRES ( 0.050 SQ MI)  
 = 87.0  
 = 0.065 INCHES/HOUR  
 = 0.56 HOURS

#### RAINFALL -- RUNOFF SUMMARY

PEAK DISCHARGE  
 TIME TO PEAK (FROM START OF RAIN)  
 RUNOFF VOLUME

= 87.5 CFS  
 = 12.3 HOURS  
 = 8.2 ACRE-FEET



```

*****
*           AMAX DATA SYSTEMS           *
*   ENGINEERING SYSTEMS DEVELOPMENT     *
*   ENVIRONMENTAL ENGINEERING           *
*           RESERVOIR ROUTING            *
*****

```

RSROUT - Version 2.01  
 FILE: BASINSP3 PRREPORT A

JANUARY 26, 1990

PROJ TITLE: PROPOSED SEDIMENT BASIN SP-3  
 SILTATION CONTROL FOR PLANT AREA  
 LOCATION: AMAX COAL INDUSTRIES INC - PENNDIANA FLD  
 SULLIVAN COUNTY, INDIANA  
 RESERVOIR: SEDIMENT BASIN SP-3  
 PLANT AREA SEDIMENT CONTROL

### RESERVOIR ROUTING - SUMMARY TABLE

(ALL TIMES ARE FROM START OF RAINFALL)

#### INFLOW PARAMETERS

WATERSHED AREA-----:	32.30 ACRES
RAINFALL RETURN PERIOD-----:	25.00 YEARS
RAINFALL DURATION-----:	24.00 HOURS
RAINFALL AMOUNT-----:	5.12 INCHES
TIME AT START OF INFLOW-----:	5.60 HOURS
PEAK INFLOW-----:	87.52 CFS
TIME TO PEAK INFLOW-----:	12.30 HOURS
INFLOW RUNOFF VOLUME-----:	8.19 ACRE-Feet
TIME TO END OF INFLOW-----:	20.60 HOURS

#### RESERVOIR PARAMETERS

RESERVOIR ELEV. AT START OF STORM--:	550.00 FEET
NORMAL POOL ELEVATION-----:	550.00 FEET
EMBANKMENT CREST ELEVATION-----:	555.00 FEET

#### STORAGE VOLUME & DISCHARGE RATE AT:

POOL ELEVATION AT STORM START:	10.49 AC-FT,	0.0 CFS
NORMAL POOL ELEVATION-----:	10.49 AC-FT,	0.0 CFS
EMBANKMENT CREST ELEVATION-----:	19.89 AC-FT,	1747.3 CFS

#### ROUTING SUMMARY

PEAK RESERVOIR ELEVATION-----:	551.04 FEET
TIME TO PEAK RESERVOIR ELEVATION--:	12.50 HOURS
OUTFLOW RATE AT PEAK ELEVATION-----:	70.88 CFS
FREEBOARD AT PEAK ELEVATION-----:	3.96 FEET
* TIME TO DRAWDOWN TO NORMAL POOL--:	8.20 HOURS
OUTFLOW RUNOFF VOLUME-----:	8.20 ACRE-Feet
ROUTING TIME INCREMENT-----:	0.10 HOURS

\* NOTE: FROM TIME OF PEAK RESERVOIR ELEVATION

RSROUT - Version 2.0I  
FILE: BASINSP3 STORAGE

JANUARY 26, 1990

PROJ TITLE: PROPOSED SEDIMENT BASIN SP-3  
SILTATION CONTROL FOR PLANT AREA  
LOCATION: AMAX COAL INDUSTRIES INC - PENNDIANA FLD  
SULLIVAN COUNTY, INDIANA  
RESERVOIR: SEDIMENT BASIN SP-3  
PLANT AREA SEDIMENT CONTROL

RESERVOIR ELEVATION VS SURFACE AREA AND STORAGE

---

RESERVOIR ELEVATION	SURFACE AREA	STORAGE CAPACITY
(FEET)	(ACRES)	(AC-FT)
540.00	0.00	0.00
542.00	0.73	0.73
545.00	1.16	3.57
550.00	1.61	10.49
555.00	2.15	19.89

RSROUT - Version 2.0i  
FILE: BASINSP3 DISCHRG A4

JANUARY 26, 1990


PROJ TITLE: PROPOSED SEDIMENT BASIN SP-3  
SILTATION CONTROL FOR PLANT AREA  
LOCATION: AMAX COAL INDUSTRIES INC - PENNDIANA FLD  
SULLIVAN COUNTY, INDIANA  
RESERVOIR: SEDIMENT BASIN SP-3  
PLANT AREA SEDIMENT CONTROL

OUTLET DEVICE: OPEN CHANNEL SPILLWAY - 10 FT BOTTOM

RESERVOIR ELEVATION VS. DISCHARGEFIRST OUTLET DEVICE


<u>RESERVOIR ELEVATION (FT)</u>	<u>DISCHARGE (CFS)</u>
550.00	0.00
550.10	1.50
550.20	4.70
550.30	9.30
550.40	15.20
550.50	22.20
550.60	30.50
550.70	39.90
550.80	50.40
550.90	62.10
551.00	62.10
551.20	104.20
551.40	138.30
551.60	177.20
551.80	221.30
552.00	270.50
553.00	600.90
554.00	1086.50
555.00	1747.30






<b>AMAX</b> COAL INDUSTRIES		PENNDIANA MINE		SEDIMENT BASIN SP-3		PLAN VIEW	
ATTACHMENT IV.E.3.		SULLIVAN COUNTY, INDIANA		SCALE 1"=100'		FILE NO.	
DRAWN	DATE	BY	REVISED	L	D	G	M
APPROVED	CONTOUR INTERVAL			GRID INT		MAP FILE NAME	
DRAWING NO.		COMPUTER SERIAL NO.		SCALE		FILE NO.	
POST OFFICE BOX 6706 INDIANAPOLIS, INDIANA 46206							

*James R. Sauer*  
1-30-90



CROSS-SECTION A-A  
1"=20'HOR. & 1"=10'VER.



*James D. Spence*

1-30-90

DRAWN	DATE	BY
1/16/90	1/16/90	1/16/90
REVISED	DATE	BY
1	1/16/90	1/16/90
APPROVED	DATE	BY
1	1/16/90	1/16/90
DATA KEY	DATE	BY
1	1/16/90	1/16/90
2	1/16/90	1/16/90
3	1/16/90	1/16/90
4	1/16/90	1/16/90
5	1/16/90	1/16/90
6	1/16/90	1/16/90
7	1/16/90	1/16/90
8	1/16/90	1/16/90
9	1/16/90	1/16/90
10	1/16/90	1/16/90

AMAX Coal Industries		AMAX	
PENNDIANA MINE		PENNDIANA MINE	
PROPOSED SEDIMENT BASIN		PROPOSED SEDIMENT BASIN	
SP-3		SP-3	
CROSS-SECTIONS		CROSS-SECTIONS	
ATTACHMENT IV.E.3.		ATTACHMENT IV.E.3.	
SULLIVAN COUNTY, INDIANA		SULLIVAN COUNTY, INDIANA	
2nd P.M.		2nd P.M.	
CONTOUR INTERVAL	GRID INT.	COMPUTER SERIAL NO.	AUTOCAD FILE NAME
DRAWING NO.	PM-9003-03-EV	SCALE	FILE NO.
D.C. BOX 8-08 INDIANAPOLIS, IN 46206-6106		90-03	

## **APPENDIX D – EXHIBIT 2**

**Sediment Basin 044**  
**Cell "A" and "B"**  
**AS-BUILT**  
**REVISED 2-25-2010**

*Farmersburg mine*

*Bear Run Pit*

*Permit S-256-2*

*25 Yr. 6 Hr. Storm Calculations*

Ken Paul

Peabody Midwest

Phone: 812-434-8586

Email: kpaul@peabodyenergy.com




## *General Information*

### *Storm Information:*

Storm Type:	NRCS Type II
Design Storm:	25 yr - 6 hr
Rainfall Depth:	3.800 inches

## Structure Networking:

Type	Stru #	(flows into)	Stru #	Musk. K (hrs)	Musk. X	Description
Pond	#1	==>	#2	0.000	0.000	SB 044, CELL "A"
Pond	#2	==>	End	0.000	0.000	SB 044, CELL "B"



*Structure Summary:*

		Immediate Contributing Area (ac)	Total Contributing Area (ac)	Peak Discharge (cfs)	Total Runoff Volume (ac-ft)
#1	In	74.200	74.200	86.90	5.71
	Out			11.38	5.72
#2	In	418.940	493.140	373.71	46.06
	Out			179.78	46.06

***Structure Detail:******Structure #1 (Pond)******SB 044, CELL "A"***

Pond Inputs:

Initial Pool Elev:	547.40 ft
Initial Pool:	173.33 ac-ft

***Emergency Spillway***

Spillway Elev	Crest Length (ft)	Left Sideslope	Right Sideslope	Bottom Width (ft)
547.40	23.00	4.80:1	5.80:1	6.20

Pond Results:

Peak Elevation:	547.72 ft
Dewater Time:	2.05 days

*Dewatering time is calculated from peak stage to lowest spillway****Elevation-Capacity-Discharge Table***

Elevation	Area (ac)	Capacity (ac-ft)	Discharge (cfs)	Dewater Time (hrs)
505.00	0.430	0.000	0.000	
507.00	0.594	1.020	0.000	
509.00	0.782	2.392	0.000	
511.00	0.997	4.167	0.000	
513.00	1.239	6.398	0.000	
515.00	1.504	9.137	0.000	
517.00	1.799	12.435	0.000	
519.00	2.117	16.346	0.000	
521.00	2.462	20.921	0.000	
523.00	2.834	26.213	0.000	
525.00	3.230	32.273	0.000	
527.00	3.684	39.182	0.000	
529.00	4.164	47.025	0.000	
531.00	4.676	55.860	0.000	
533.00	5.216	65.747	0.000	
535.00	5.786	76.744	0.000	
537.00	6.387	88.912	0.000	
539.00	7.014	102.307	0.000	

Elevation	Area (ac)	Capacity (ac-ft)	Discharge (cfs)	Dewater Time (hrs)
541.00	7.675	116.991	0.000	
543.00	8.362	133.023	0.000	
545.00	9.081	150.461	0.000	
547.00	9.828	169.365	0.000	
547.40	9.980	173.327	0.000	Spillway #1
547.72	10.322	176.671	11.379	45.65 Peak Stage
549.00	11.207	190.267	57.655	
550.00	12.010	201.873	171.633	

\*Designates time(s) to dewater have been extrapolated beyond the 50 hour hydrograph limit.

## Detailed Discharge Table

Elevation (ft)	Emergency Spillway (cfs)	Combined Total Discharge (cfs)
505.00	0.000	0.000
507.00	0.000	0.000
509.00	0.000	0.000
511.00	0.000	0.000
513.00	0.000	0.000
515.00	0.000	0.000
517.00	0.000	0.000
519.00	0.000	0.000
521.00	0.000	0.000
523.00	0.000	0.000
525.00	0.000	0.000
527.00	0.000	0.000
529.00	0.000	0.000
531.00	0.000	0.000
533.00	0.000	0.000
535.00	0.000	0.000
537.00	0.000	0.000
539.00	0.000	0.000
541.00	0.000	0.000
543.00	0.000	0.000
545.00	0.000	0.000
547.00	0.000	0.000
547.40	0.000	0.000
549.00	57.655	57.655
550.00	171.633	171.633

Structure #2 (Pond)

SB 044, CELL "B"

Pond Inputs:

Initial Pool Elev:	519.40 ft
Initial Pool:	103.41 ac-ft

Emergency Spillway

Spillway Elev	Crest Length (ft)	Left Sideslope	Right Sideslope	Bottom Width (ft)
519.40	44.50	5.50:1	3.80:1	20.10

Pond Results:

Peak Elevation:	521.06 ft
Dewater Time:	0.15 days

*Dewatering time is calculated from peak stage to lowest spillway*

Elevation-Capacity-Discharge Table

Elevation	Area (ac)	Capacity (ac-ft)	Discharge (cfs)	Dewater Time (hrs)
472.00	0.100	0.000	0.000	
474.00	0.156	0.254	0.000	
476.00	0.223	0.631	0.000	
478.00	0.303	1.155	0.000	
480.00	0.394	1.850	0.000	
482.00	0.497	2.739	0.000	
484.00	0.612	3.847	0.000	
486.00	0.739	5.197	0.000	
488.00	0.880	6.814	0.000	
490.00	1.032	8.723	0.000	
492.00	1.196	10.948	0.000	
494.00	1.371	13.513	0.000	
496.00	1.559	16.442	0.000	
498.00	1.759	19.757	0.000	
500.00	1.970	23.484	0.000	
502.00	2.299	27.748	0.000	
504.00	2.653	32.695	0.000	
506.00	3.031	38.375	0.000	
508.00	3.436	44.838	0.000	
510.00	3.865	52.135	0.000	
512.00	4.320	60.316	0.000	

Elevation	Area (ac)	Capacity (ac-ft)	Discharge (cfs)	Dewater Time (hrs)
514.00	5.087	69.713	0.000	
516.00	5.917	80.706	0.000	
518.00	6.808	93.421	0.000	
519.40	7.470	103.412	0.000	Spillway #1
520.00	7.858	108.010	65.000	0.86*
521.06	8.587	117.047	179.780	2.85 Peak Stage
522.00	9.220	125.069	281.674	
523.00	9.870	134.612	549.049	

\*Designates time(s) to dewater have been extrapolated beyond the 50 hour hydrograph limit.

## Detailed Discharge Table

Elevation (ft)	Emergency Spillway (cfs)	Combined Total Discharge (cfs)
472.00	0.000	0.000
474.00	0.000	0.000
476.00	0.000	0.000
478.00	0.000	0.000
480.00	0.000	0.000
482.00	0.000	0.000
484.00	0.000	0.000
486.00	0.000	0.000
488.00	0.000	0.000
490.00	0.000	0.000
492.00	0.000	0.000
494.00	0.000	0.000
496.00	0.000	0.000
498.00	0.000	0.000
500.00	0.000	0.000
502.00	0.000	0.000
504.00	0.000	0.000
506.00	0.000	0.000
508.00	0.000	0.000
510.00	0.000	0.000
512.00	0.000	0.000
514.00	0.000	0.000
516.00	0.000	0.000
518.00	0.000	0.000
519.40	0.000	0.000

Elevation (ft)	Emergency Spillway (cfs)	Combined Total Discharge (cfs)
520.00	65.000	65.000
522.00	281.674	281.674
523.00	549.049	549.049



### *Subwatershed Hydrology Detail:*

Stru #	SWS #	SWS Area (ac)	Time of Conc (hrs)	Musk K (hrs)	Musk X	Curve Number	UHS	Peak Discharge (cfs)	Runoff Volume (ac-ft)
#1	1	74.200	0.174	0.000	0.000	69.000	M	86.90	5.712
$\Sigma$		74.200						86.90	5.712
#2	1	418.940	0.631	0.000	0.000	74.000	M	364.68	40.338
$\Sigma$		493.140						373.71	46.058

### *Subwatershed Time of Concentration Details:*

Stru #	SWS #	Land Flow Condition	Slope (%)	Vert. Dist. (ft)	Horiz. Dist. (ft)	Velocity (fps)	Time (hrs)
#1	1	3. Short grass pasture	2.60	13.00	500.00	1.280	0.108
		8. Large gullies, diversions, and low flowing streams	2.71	32.00	1,180.00	4.940	0.066
#1	1	<b>Time of Concentration:</b>					<b>0.174</b>
#2	1	4. Cultivated, straight row	2.20	11.00	500.00	1.320	0.105
		8. Large gullies, diversions, and low flowing streams	1.04	60.00	5,782.00	3.050	0.526
#2	1	<b>Time of Concentration:</b>					<b>0.631</b>

# Sediment Basin Design Summary

25-Feb-10

## I. General Information

Mine: Bear Run Pit, Permit #256-2  
Basin: SB 044 CELL "B" As-built  
Basin Type: Incised  
Examination Exempt: Yes

## II. Design Parameters:

Design Storm Event : (10yr/24hr) 4.45  
Runoff Area (RA) (Treatment and Detention) 418.94  
Runoff Coefficient (RC) 0.52

## III. Runoff Calculation:

$$RV = RE \text{ (in / 24hr)} * 1\text{ft}/12 \text{ in} * \text{Runoff Area (ac)} * 43,560 \text{ sq ft /ac} * RC$$

where: RV = runoff volume (cubic ft/24hr)

RE = runoff design event (inches/24hr)

RC = runoff coefficient

$$RV = \boxed{3497730} \text{ cubic ft /24hr} \quad \boxed{80.30} \text{ acre ft}$$

## IV. Treatment Volume Calculation:

Detention Time: DT 10 hours  
Sediment Volume: SV 210427 cubic ft  
Pit Pumpage Volume: PV 500 gpm

$$MCV = RV \text{ cf / 24hr} * 1\text{day}/24\text{hr} * DT \text{ hr} + PV \text{ gpm} \\ * 1440 \text{ min/day} * 1\text{day}/24\text{hr} * 0.1337 \text{ cf/gal} * DT \text{ hr} + SV \text{ cf}$$

$$\text{Minimum Compliance volume} = \boxed{1707692} \text{ cubic ft} \quad \boxed{39.20} \text{ acre ft}$$

Basin Freeboard: 2.0 ft minimum at pool  
Basin Surface area: 7.47 acres 325393 sq ft  
Basin Minimum Average depth: 5.25 ft

**Sediment Basin Design:**  
**Universal Soil Loss Calculation:**

25-Feb-10

Mine: Bear Run Pit, Permit #256-2

Basin: SB 044 CELL "B" As-built

**Soil Loss per Unit Area:**

$$A = R * K * LS * CP$$

$$A = 9.04 \text{ tons/acre}$$

where: A = Soil loss per acre (tons/acre)

R = Rainfall-Erosivity Factor 200

K = Soil Erodibility Factor 0.43

LS = Length Slope Factor 0.47

CP = Cropping Practice Factor 0.22

**LS Factor Calculation**

$$LS = (FSL/72.6)^m * ((430x^2 + 30x + 0.43) / 6.613))$$

$$0.47$$

where: FSL = Field Slope Length

6282.00

x = Field Slope Ratio

0.0113

m = slope factor

0.3

slope < 3% m=0.3 , = 4% m=0.4, >5% m=0.5

**CP Weighted Factor Calculation**

Ground Cover Description	CP Value	Area (ac)	CP*ac
Active Disturbed area	0.90	67.94	61.15
Reclaimed or Undisturbed	0.09	351.00	31.59
		418.94	92.74
			0.22 Weighted CP

**Sediment Delivery Ratio:**

$$D = Da * Dv * Dc * Dp$$

$$D = 0.25$$

where: D = sediment delivery ratio

0.25

Da = area delivery ratio

0.50

Dv = Vegetation trapping factor

1.00

Dc = Channelization factor

0.50

Dp = pit deposition factor

1.00

**Sediment Yield From Design Watershed:**

$$Y = A * D$$

$$Y = 2.26 \text{ tons/acre}$$

where: Y = Watershed Sediment Yield (Tons / Acre)

A = Soil loss per area (Tons / Acre)

D = Sediment Delivery Ratio

Life of Basin 10.0 years

**Sediment Yield Conversion Ac ft / ac year:**

$$Y2 (\text{ac ft} / \text{ac yr}) = (Y \text{ t/ac} * 2000 \text{ lb/t}) / (90 \text{ lb/cubic ft} * 43560 \text{ sq ft} / \text{ac})$$

$$Y2 = 0.00115 \text{ ac ft} / \text{ac yr}$$


**Sediment Storage Calculation:**

$$SL = RA * Y2 * YR * 43560 \text{ Design Sediment Storage} =$$

$$210427 \text{ cubic ft}$$

# SB 044 Cell "B" As-Built Volume Summary



Surface Area: 7.47 acres  
 Impounded volume: 0.0 ac-ft  
 As-Built Treatment volume: 103.83 ac ft  
 Minimum Compliance Volume: 39.20 ac ft  
 Surplus Volume: 64.63 ac ft



HOR. 1" = 200'

Black Beauty Coal Company	DATE: 2-25-2010	REVISION NO.:	DATE:
	SCALE: 1 in = 200 ft	NOTES: Surveyed by Donnie Oxidine	
	SHEET 1 OF 2		


Sediment Control Basin SB 044 Cell "B"  
 As-Built Plan View  
 Farmersburg Mine, Bear Run East Pit, Permit #2556-2




# Basin SB 044 Cell "B" As-Built Combination Spillway



Emergency Spillway @ 519.4'  
Channel Lining: 6 inch Rock Rip-Rap



NOT TO SCALE



Brian D. Butts  
2/25/10

Black Beauty Coal Company

DATE: 2-25-2010

REVISION NO: DATE:

Sediment Control Basin SB 044 Cell "B"  
As-built Cross-sections and Spillway Section  
Farmersburg Mine, Bear Run East Pit, Permit #256-2

SCALE: As-Noted

NOTES: Surveyed by Donnie Oxidine

SHEET 2 OF 2

## **APPENDIX D – EXHIBIT 3**

# Sediment Basin 058

## As-built

*Bear Run Mine*

*Permit S-256*

*25 Yr. 6 Hr. Storm Calculations*

Ken Paul

## *General Information*


### *Storm Information:*

Storm Type:	NRCS Type II
Design Storm:	25 yr - 6 hr
Rainfall Depth:	3.800 inches



## Structure Networking:

Type	Stru #	(flows into)	Stru #	Musk. K (hrs)	Musk. X	Description
Pond	#1	==>	#2	0.000	0.000	SB 058 CELL "B"
Pond	#2	==>	End	0.000	0.000	SB 058 CELL "A"



*Structure Summary:*

		Immediate Contributing Area (ac)	Total Contributing Area (ac)	Peak Discharge (cfs)	Total Runoff Volume (ac-ft)
#1	In	28.400	28.400	48.05	3.18
	Out			33.28	3.18
#2	In	65.400	93.800	141.65	10.52
	Out			53.79	10.52

## *Structure Detail:*

### Structure #1 (Pond)

*SB 058 CELL "B"*

Pond Inputs:

Initial Pool Elev:	581.00 ft
Initial Pool:	3.40 ac-ft

### Emergency Spillway

Spillway Elev	Crest Length (ft)	Left Sideslope	Right Sideslope	Bottom Width (ft)
581.00	20.00	3.50:1	2.90:1	11.80

Pond Results:

Peak Elevation:	581.57 ft
Dewater Time:	0.20 days

*Dewatering time is calculated from peak stage to lowest spillway*

### Elevation-Capacity-Discharge Table

Elevation	Area (ac)	Capacity (ac-ft)	Discharge (cfs)	Dewater Time (hrs)
575.00	0.220	0.000	0.000	
577.00	0.403	0.614	0.000	
578.00	0.510	1.070	0.000	
579.00	0.680	1.663	0.000	
581.00	1.070	3.397	0.000	Spillway #1
581.57	1.187	4.112	33.282	4.75 Peak Stage
583.00	1.470	5.927	117.738	

### Detailed Discharge Table

Elevation (ft)	Emergency Spillway (cfs)	Combined Total Discharge (cfs)
575.00	0.000	0.000
577.00	0.000	0.000
578.00	0.000	0.000
579.00	0.000	0.000

Elevation (ft)	Emergency Spillway (cfs)	Combined Total Discharge (cfs)
581.00	0.000	0.000
583.00	117.738	117.738

Structure #2 (Pond)

SB 058 CELL "A"

Pond Inputs:

Initial Pool Elev:	573.60 ft
Initial Pool:	13.70 ac-ft

Straight Pipe

Barrel Diameter (in)	Barrel Length (ft)	Barrel Slope (%)	Manning's n	Spillway Elev (ft)	Entrance Loss Coefficient	Tailwater Depth (ft)
24.00	80.00	16.60	0.0150	573.60	0.90	0.00

Emergency Spillway

Spillway Elev	Crest Length (ft)	Left Sideslope	Right Sideslope	Bottom Width (ft)
574.60	38.00	6.40:1	4.60:1	14.70

Pond Results:

Peak Elevation:	575.44 ft
Dewater Time:	0.40 days

*Dewatering time is calculated from peak stage to lowest spillway*

Elevation-Capacity-Discharge Table

Elevation	Area (ac)	Capacity (ac-ft)	Discharge (cfs)	Dewater Time (hrs)
559.00	0.040	0.000	0.000	
560.00	0.380	0.181	0.000	
561.00	0.438	0.590	0.000	
563.00	0.563	1.589	0.000	
565.00	0.704	2.853	0.000	
567.00	0.860	4.415	0.000	
569.00	1.165	6.432	0.000	
571.00	1.514	9.103	0.000	

Elevation	Area (ac)	Capacity (ac-ft)	Discharge (cfs)	Dewater Time (hrs)
573.00	1.907	12.516	0.000	
573.60	2.030	13.697	0.000	Spillway #1
574.60	2.415	15.916	4.189	6.41* Spillway #2
575.00	2.573	16.914	27.365	2.25
575.44	2.762	18.149	53.793	1.05 Peak Stage
576.00	2.990	19.693	86.826	
576.50	3.200	21.240	150.607	

*\*Designates time(s) to dewater have been extrapolated beyond the 50 hour hydrograph limit.*

## Detailed Discharge Table

Elevation (ft)	Straight Pipe (cfs)	Emergency Spillway (cfs)	Combined Total Discharge (cfs)
559.00	0.000	0.000	0.000
560.00	0.000	0.000	0.000
561.00	0.000	0.000	0.000
563.00	0.000	0.000	0.000
565.00	0.000	0.000	0.000
567.00	0.000	0.000	0.000
569.00	0.000	0.000	0.000
571.00	0.000	0.000	0.000
573.00	0.000	0.000	0.000
573.60	0.000	0.000	0.000
574.60	(3)>4.189	0.000	4.189
575.00	(3)>6.942	20.422	27.365
576.00	(4)>15.350	71.475	86.826
576.50	(5)>18.875	131.732	150.607

### *Subwatershed Hydrology Detail:*

Stru #	SWS #	SWS Area (ac)	Time of Conc (hrs)	Musk K (hrs)	Musk X	Curve Number	UHS	Peak Discharge (cfs)	Runoff Volume (ac-ft)
#1	1	28.400	0.175	0.000	0.000	77.000	M	48.05	3.181
$\Sigma$		<b>28.400</b>						<b>48.05</b>	<b>3.181</b>
#2	1	65.400	0.132	0.000	0.000	77.000	M	112.32	7.339
$\Sigma$		<b>93.800</b>						<b>141.65</b>	<b>10.520</b>

### *Subwatershed Time of Concentration Details:*

Stru #	SWS #	Land Flow Condition	Slope (%)	Vert. Dist. (ft)	Horiz. Dist. (ft)	Velocity (fps)	Time (hrs)
#1	1	4. Cultivated, straight row	2.40	12.00	500.00	1.380	0.100
		8. Large gullies, diversions, and low flowing streams	1.76	19.00	1,080.00	3.970	0.075
<b>#1</b>	<b>1</b>	<b>Time of Concentration:</b>					<b>0.175</b>
#2	1	4. Cultivated, straight row	3.38	11.00	325.00	1.640	0.055
		8. Large gullies, diversions, and low flowing streams	3.36	51.40	1,532.00	5.490	0.077
<b>#2</b>	<b>1</b>	<b>Time of Concentration:</b>					<b>0.132</b>

## Sediment Basin Design Summary

27-Feb-12

### I. General Information

Mine: Bear Run Pit, Permit #256-4  
Basin: SB 058 As-built

Basin Type: Incised  
Examination Exempt: Yes

### II. Design Parameters:

Design Storm Event : (10yr/24hr) 4.45  
Runoff Area (RA) (Treatment and Detention) 93.80  
Runoff Coefficient (RC) 0.52

### III. Runoff Calculation:

$$RV = RE \text{ (in / 24hr)} * 1\text{ft}/12 \text{ in} * \text{Runoff Area (ac)} * 43,560 \text{ sq ft /ac} * RC$$

where: RV = runoff volume (cubic ft/24hr)

RE = runoff design event (inches/24hr)

RC = runoff coefficient

$$RV = \boxed{783136} \text{ cubic ft /24hr} \quad \boxed{17.98} \text{ acre ft}$$

### IV. Treatment Volume Calculation:

Detention Time: DT 10 hours  
Sediment Volume: SV 315078 cubic ft  
Pit Pumpage Volume: PV 500 gpm

$$MCV = RV \text{ cf / 24hr} * 1\text{day}/24\text{hr} * DT \text{ hr} + PV \text{ gpm} \\ * 1440 \text{ min/day} * 1\text{day}/24\text{hr} * 0.1337 \text{ cf/gal} * DT \text{ hr} + SV \text{ cf}$$

$$\text{Minimum Compliance volume} = \boxed{681443} \text{ cubic ft} \quad \boxed{15.64} \text{ acre ft}$$

Basin Freeboard: 2.0 ft minimum at pool  
Basin Surface area: 3.10 acres 135036 sq ft  
Basin Minimum Average depth 5.05 ft

**Sediment Basin Design:**  
**Universal Soil Loss Calculation:**

27-Feb-12

**Mine:** Bear Run Pit, Permit #256-4

**Basin:** SB 058 As-built

**Soil Loss per Unit Area:**

$$A = R * K * LS * CP$$

where: A = Soil loss per acre (tons/acre)

R = Rainfall-Erosivity Factor	200
K = Soil Erodibility Factor	0.43
LS = Length Slope Factor	3.23
CP = Cropping Practice Factor	0.44

**LS Factor Calculation**

$$LS = (FSL/72.6)^m * ((430x^2 + 30x + 0.43) / 6.613))$$

3.23

where: FSL = Field Slope Length 1857.00

x = Field Slope Ratio 0.0653

m = slope factor 0.5

slope < 3% m=0.3 , = 4% m=0.4, >5% m=0.5

**CP Weighted Factor Calculation**

Ground Cover Description	CP Value	Area (ac)	CP*ac
Active Disturbed area	0.90	40.00	36.00
Reclaimed or Undisturbed	0.09	53.80	4.84
		93.80	40.84 0.44

**Sediment Delivery Ratio:**

$$D = Da * Dv * Dc * Dp$$

D= 0.25

where: D = sediment delivery ratio 0.25

Da = area delivery ratio 0.50

Dv = Vegetation trapping factor 1.00

Dc = Channelization factor 0.50

Dp = pit deposition factor 1.00

**Sediment Yield From Design Watershed:**

$$Y = A * D$$

Y= 30.23 tons/acre

where: Y = Watershed Sediment Yield (Tons / Acre)

A = Soil loss per area (Tons / Acre)

D = Sediment Delivery Ratio

Life of Basin 5.0 years

**Sediment Yield Conversion Ac ft / ac year:**

$$Y2 \text{ (ac ft / ac yr)} = (Y \text{ t/ac} * 2000 \text{ lb/t}) / (90 \text{ lb/cubic ft} * 43560 \text{ sq ft / ac})$$

$$Y2 = 0.01542 \text{ ac ft / ac yr}$$

**Sediment Storage Calculation:**


$$SL = RA * Y2 * YR * 43560 \text{ Design Sediment Storage} =$$

315078 cubic ft



# SB 058 Cell "A" and Cell "B" As-built Volume Summary

Surface Area: Cell "A" 2.03 ac., Cell "B" 1.07 ac.  
 Impounded volume: Cell "A" 5.20 ac ft, Cell "B" 3.30 ac ft  
 As-built Treatment volume: Cell "A" and "B" 16.49 ac ft  
 Minimum Compliance Volume: Cell "A" and "B" 15.64 ac ft  
 Surplus Volume: 0.85 ac ft



LLOYD A. SHORT  
 REGISTERED  
 No. 60021270  
 STATE OF INDIANA  
 PROFESSIONAL ENGINEER  
 3/5/12

HOR. 1" = 200'

**Peabody Midwest Mining LLC**

Sediment Control Basin SB 058, Cell "A" and Cell "B"  
 As-built Plan View  
 Bear Run Mine, Permit #256

DATE: 2-23-2012

REVISION NO.:


DATE:

SCALE: 1 in = 100 ft


NOTES:

SHEET 1 OF 2


Cross-section A - A'





# Basin SB 058, Cell "B" Combination Spillway



Cross-section B - B'



# Basin SB 058, Cell "A" Emergency and Primary Spillway



**Peabody Midwest Mining LLC**

Sediment Control Basin SB 058, Cell "A" and Cell "B"  
As-built Cross-sections and Spillway Section  
Bear Run Mine, Permit #256-4

DATE: 2-23-2012

SCALE: As-Noted

SHEET 2 OF 2

*Lloyd A. Short*  
3/5/12  
DATE:

NOTES:

## **APPENDIX D – EXHIBIT 4**

# PEABODY MIDWEST MINING, LLC

## IMPOUNDMENT EXAMINATION EXEMPTION REQUEST

MINE NAME Bear Run Mine  
PERMIT NUMBER S-256-4  
IMPOUNDMENT ID SB 062


The above referenced impoundment is exempt from the annual examination and certification requirements under 312 IAC 25-6-20-(a)(9)E because of the following: 1) The structure is maintained as designed and in accordance with 312 IAC 25-6-20, 2) No appearance(s) of instability, structural weakness or other hazardous conditions have been observed and 3) The structure does not create a potential threat to public health and safety or threaten significant environmental harm.

### Specific Exemption:

- ☒ Incised Impoundment  
☐ Impounding Structure < 5 ft above upstream toe, < 20 ac/ft storage volume.  
☐ Impoundment which does not facilitate mining or reclamation:


Sewage lagoons  
Landscaping pond  
Pool or wetland in replaced stream channel  
Existing impoundment not yet used to facilitate mining  
Ephemeral water body  
Active mining pit  
Differential settlement pool

Note: Impoundment previously Identified as FCI #1 under S-00010 and was certified as-built in 4/6/98 approved NSIG#154 of permit S-00010 as well as exempted from quarterly examination and annual recertification. The impoundment has not been altered from its original configuration.

  
Rudolph J. Notich, P.E. 19400077

Date: 7-7-11

SEAL:



# Sediment Basin Design Summary

09-Jun-09



## I. General Information

Mine: Bear Run Pit, Permit #256-4  
Basin: SB 062

Basin Type: Incised  
Examination Exempt: Yes

## II. Design Parameters:

Design Storm Event : (10yr/24hr) 4.45  
Runoff Area (RA) (Treatment and Detention) 503.00  
Runoff Coefficient (RC) 0.52

## III. Runoff Calculation:

$$RV = RE \text{ (in / 24hr)} * 1 \text{ ft/12 in} * \text{Runoff Area (ac)} * 43,560 \text{ sq ft/ac} * RC$$

where: RV = runoff volume (cubic ft/24hr)  
RE = runoff design event (inches/24hr)  
RC = runoff coefficient

RV = 4199547 cubic ft /24hr 96.41 acre ft

## IV. Treatment Volume Calculation:

Detention Time: DT 10 hours  
Sediment Volume: SV 1536499 cubic ft  
Pit Pumpage Volume: PV 500 gpm

$$MCV = RV \text{ cf / 24hr} * 1 \text{ day/24hr} * DT \text{ hr} + PV \text{ gpm} \\ * 1440 \text{ min/day} * 1 \text{ day/24hr} * 0.1337 \text{ cf/gal} * DT \text{ hr} + SV \text{ cf}$$

Minimum Compliance volume= 3326141 cubic ft 76.36 acre ft

Basin Freeboard: 2.0 ft minimum at pool  
Basin Surface area: 35.50 acres 1546380 sq ft  
Basin Minimum Average depth 2.15 ft

**Sediment Basin Design:**  
**Universal Soil Loss Calculation:**

06-Jun-09

Mine: Bear Run Pit, Permit #256-4

Basin: SB 062

**Soil Loss per Unit Area:**

$$A = R * K * LS * CP$$

$$A = 109.97 \text{ tons/acre}$$

where: A = Soil loss per acre (tons/acre)

R = Rainfall-Erosivity Factor 200

K = Soil Erodibility Factor 0.43

LS = Length Slope Factor 5.84

CP = Cropping Practice Factor 0.22

**LS Factor Calculation**

$$LS = (FSL/72.6)^m * ((430x^2 + 30x + 0.43) / 6.613))$$

5.84

where: FSL = Field Slope Length

4019.00

x = Field Slope Ratio

0.0760

m = slope factor

0.5

slope < 3% m=0.3 , = 4% m=0.4, >5% m=0.5

**CP Weighted Factor Calculation**

Ground Cover Description	CP Value	Area (ac)	CP*ac
Active Disturbed area	0.90	80.00	72.00
Reclaimed or Undisturbed	0.09	423.00	38.07
		503.00	110.07
			0.22 Weighted CP

**Sediment Delivery Ratio:**

$$D = Da * Dv * Dc * Dp$$

$$D = 0.25$$

where: D = sediment delivery ratio

0.25

Da = area delivery ratio

0.50

Dv = Vegetation trapping factor

1.00

Dc = Channelization factor

0.50

Dp = pit deposition factor

1.00

**Sediment Yield From Design Watershed:**

$$Y = A * D$$

$$Y = 27.49 \text{ tons/acre}$$

where: Y = Watershed Sediment Yield (Tons / Acre)

A = Soil loss per area (Tons / Acre)

D = Sediment Delivery Ratio

Life of Basin 5.0 years

**Sediment Yield Conversion Ac ft / ac year:**

$$Y2 \text{ (ac ft / ac yr)} = (Y \text{ t/ac} * 2000 \text{ lb/t}) / (90 \text{ lb/cubic ft} * 43560 \text{ sq ft / ac})$$

$$Y2 = 0.01403 \text{ ac ft / ac yr}$$



**Sediment Storage Calculation:**

$$SL = RA * Y2 * YR * 43560 \text{ Design Sediment Storage} =$$

$$1536499 \text{ cubic ft}$$

# SB 062 Dam Volume Summary


Surface Area: 35.5 acres
Impounded volume: 0.0 ac ft
Design Treatment volume: 942.43 ac ft
Minimum Compliance Volume: 76.36 ac ft
Surplus Volume: 866.07 ac ft




HOR. 1" = 400'

Black Beauty Coal Company		DATE: 6-3-2009	REVISION NO.:	DATE:
Sediment Control Basin SB 062		SCALE: 1 in = 400 ft	NOTES:	
Plan View		SHEET 1 OF 2		
Bear Run Mine, Permit #256-4				


# Cross-section A - A'




# Cross-section B - B'



## SB 062 Combination Spillway



NOT TO SCALE



Black Beauty Coal Company

Sediment Control Basin SB 062  
Cross-sections and Spillway Section  
Bear Run Mine, Permit #256-4

DATE: 6-3-2009

REVISION NO.:

DATE:

SCALE: As-Noted

NOTES:

SHEET 2 OF 2



## **APPENDIX D – EXHIBIT 5**

# **Sediment Basin 053** **Cell "A"**

*Bear Run Mine*  
*Permit S-256*  
*25 Yr. 6 Hr. Storm Calculations*

Ken Paul

Peabody Midwest

Phone: 812-434-8586  
Email: Kpaul@peabodyenergy.com

## *General Information*

### *Storm Information:*

Storm Type:	NRCS Type II
Design Storm:	25 yr - 6 hr
Rainfall Depth:	3.800 inches

### *Structure Networking:*

Type	Stru #	(flows into)	Stru #	Musk. K (hrs)	Musk. X	Description
Pond	#1	==>	End	0.000	0.000	SB 053 Cell "A"

#1
Pond

*Structure Summary:*

		Immediate Contributing Area (ac)	Total Contributing Area (ac)	Peak Discharge (cfs)	Total Runoff Volume (ac-ft)
#1	In			659.02	59.01
	Out	493.000	493.000	76.32	58.09

## *Structure Detail:*

### Structure #1 (Pond)

*SB 053 Cell "A"*

Pond Inputs:

Initial Pool Elev:	520.00 ft
Initial Pool:	658.24 ac-ft

### Emergency Spillway

Spillway Elev	Crest Length (ft)	Left Sideslope	Right Sideslope	Bottom Width (ft)
520.00	20.00	3.00:1	3.00:1	12.00

Pond Results:

Peak Elevation:	521.40 ft
Dewater Time:	0.66 days

*Dewatering time is calculated from peak stage to lowest spillway*

### Elevation-Capacity-Discharge Table

Elevation	Area (ac)	Capacity (ac-ft)	Discharge (cfs)	Dewater Time (hrs)
475.00	0.540	0.000	0.000	
477.00	1.737	2.164	0.000	
479.00	3.610	7.398	0.000	
480.00	4.800	11.589	0.000	
481.00	5.359	16.666	0.000	
483.00	6.568	28.572	0.000	
485.00	7.900	43.020	0.000	
487.00	8.755	59.668	0.000	
489.00	9.651	78.067	0.000	
491.00	10.592	98.304	0.000	
493.00	11.577	120.466	0.000	
495.00	12.603	144.639	0.000	
497.00	13.677	170.912	0.000	
499.00	14.792	199.374	0.000	
501.00	15.951	230.110	0.000	
503.00	17.155	263.210	0.000	
505.00	18.400	298.758	0.000	

Elevation	Area (ac)	Capacity (ac-ft)	Discharge (cfs)	Dewater Time (hrs)
507.00	19.784	336.934	0.000	
509.00	21.219	377.928	0.000	
511.00	22.703	421.841	0.000	
513.00	24.237	468.772	0.000	
515.00	25.821	518.822	0.000	
517.00	27.455	572.090	0.000	
519.00	29.139	628.676	0.000	
520.00	30.000	658.245	0.000	Spillway #1
521.00	30.579	688.534	31.357	11.69*
521.40	30.816	700.870	76.325	4.05 Peak Stage
523.00	31.753	750.862	258.549	
525.00	32.950	815.562	721.469	

\*Designates time(s) to dewater have been extrapolated beyond the 50 hour hydrograph limit.

Detailed Discharge Table

Elevation (ft)	Emergency Spillway (cfs)	Combined Total Discharge (cfs)
475.00	0.000	0.000
477.00	0.000	0.000
479.00	0.000	0.000
480.00	0.000	0.000
481.00	0.000	0.000
483.00	0.000	0.000
485.00	0.000	0.000
487.00	0.000	0.000
489.00	0.000	0.000
491.00	0.000	0.000
493.00	0.000	0.000
495.00	0.000	0.000
497.00	0.000	0.000
499.00	0.000	0.000
501.00	0.000	0.000
503.00	0.000	0.000
505.00	0.000	0.000
507.00	0.000	0.000
509.00	0.000	0.000
511.00	0.000	0.000
513.00	0.000	0.000

Elevation (ft)	Emergency Spillway (cfs)	Combined Total Discharge (cfs)
515.00	0.000	0.000
517.00	0.000	0.000
519.00	0.000	0.000
520.00	0.000	0.000
521.00	31.357	31.357
523.00	258.549	258.549
525.00	721.469	721.469



### *Subwatershed Hydrology Detail:*

Stru #	SWS #	SWS Area (ac)	Time of Conc (hrs)	Musk K (hrs)	Musk X	Curve Number	UHS	Peak Discharge (cfs)	Runoff Volume (ac-ft)
#1	1	493.000	0.445	0.000	0.000	79.000	M	659.02	59.013
$\Sigma$		493.000						659.02	59.013

### *Subwatershed Time of Concentration Details:*

Stru #	SWS #	Land Flow Condition	Slope (%)	Vert. Dist. (ft)	Horiz. Dist. (ft)	Velocity (fps)	Time (hrs)
#1	1	4. Cultivated, straight row	4.00	20.00	500.00	1.780	0.078
		8. Large gullies, diversions, and low flowing streams	1.85	100.00	5,405.11	4.080	0.367
#1	1	<b>Time of Concentration:</b>					<b>0.445</b>

Sediment Basin Design Summary**I. General Information**

Mine: Bear Run Pit, Permit #256-4  
 Basin: SB 053 cell "A"

Basin Type: Incised  
 Examination Exempt: Yes

**II. Design Parameters:**

Design Storm Event : (10yr/24hr) 4.45  
 Runoff Area (RA) (Treatment and Detention) 493.00  
 Runoff Coefficient (RC) 0.52

**III. Runoff Calculation:**

$$RV = RE \text{ (in / 24hr)} * 1\text{ft}/12 \text{ in} * \text{Runoff Area (ac)} * 43,560 \text{ sq ft /ac} * RC$$

where: RV = runoff volume (cubic ft/24hr)  
 RE = runoff design event (inches/24hr)  
 RC = runoff coefficient

$$RV = \boxed{4116057} \text{ cubic ft /24hr} \quad \boxed{94.49} \text{ acre ft}$$

**IV. Treatment Volume Calculation:**

Detention Time: DT 10 hours  
 Sediment Volume: SV 2267880 cubic ft  
 Pit Pumpage Volume: PV 500 gpm

$$MCV = RV \text{ cf / 24hr} * 1\text{day}/24\text{hr} * DT \text{ hr} + PV \text{ gpm} \\
* 1440 \text{ min/day} * 1\text{day}/24\text{hr} * 0.1337 \text{ cf/gal} * DT \text{ hr} + SV \text{ cf}$$

$$\text{Minimum Compliance volume} = \boxed{4022739} \text{ cubic ft} \quad \boxed{92.35} \text{ acre ft}$$

Basin Freeboard: 2.0 ft minimum at pool  
 Basin Surface area: 30.00 acres 1306800 sq ft  
 Basin Minimum Average depth: 3.08 ft

**Sediment Basin Design:**  
**Universal Soil Loss Calculation:**

Mine: Bear Run Pit, Permit #256-4

Basin: SB 053 cell "A"

**Soil Loss per Unit Area:**

$$A = R * K * LS * CP$$

where: A = Soil loss per acre (tons/acre)

R = Rainfall-Erosivity Factor	200
K = Soil Erodibility Factor	0.43
LS = Length Slope Factor	5.72
CP = Cropping Practice Factor	0.34

$$A = 165.61 \text{ tons/acre}$$

**LS Factor Calculation**

$$LS = (FSL/72.6)^m * ((430x^2 + 30x + 0.43) / 6.613)$$

where: FSL = Field Slope Length 5905.00

x = Field Slope Ratio 0.0650

m = slope factor 0.5

slope < 3% m=0.3 , = 4% m=0.4, >5% m=0.5

**CP Weighted Factor Calculation**

Ground Cover Description	CP Value	Area (ac)	CP*ac
Active Disturbed area	0.90	150.00	135.00
Reclaimed or Undisturbed	0.09	343.00	30.87
		493.00	165.87
			0.34 Weighted CP

**Sediment Delivery Ratio:**

$$D = Da * Dv * Dc * Dp$$

$$D = 0.25$$

where: D = sediment delivery ratio 0.25

Da = area delivery ratio 0.50

Dv = Vegetation trapping factor 1.00

Dc = Channelization factor 0.50

Dp = pit deposition factor 1.00

**Sediment Yield From Design Watershed:**

$$Y = A * D$$

$$Y = 41.40 \text{ tons/acre}$$

where: Y = Watershed Sediment Yield (Tons / Acre)

A = Soil loss per area (Tons / Acre)

D = Sediment Delivery Ratio

Life of Basin 5.0 years

**Sediment Yield Conversion Ac ft / ac year:**

$$Y2 (\text{ac ft / ac yr}) = (Y \text{ t/ac} * 2000 \text{ lb/t}) / (90 \text{ lb/cubic ft} * 43560 \text{ sq ft / ac})$$

$$Y2 = 0.02112 \text{ ac ft / ac yr}$$


**Sediment Storage Calculation:**

$$SL = RA * Y2 * YR * 43560 \text{ Design Sediment Storage} =$$


$$2267880 \text{ cubic ft}$$

# SB 053 Cell "A"

Surface Area: 30.0 acres  
 Impounded volume: 0.0 ac ft  
 Design Treatment volume: 644.13 ac ft  
 Minimum Compliance Volume: 92.35 ac ft  
 Surplus Volume : 551.78 ac ft



HOR. 1" = 500'



3-16-11

Peabody Midwest Mining LLC

Sediment Control Basin SB 053 Cell "A"

Plan View  
 Bear Run Mine, Permit #256

DATE: 3-3-2011

SCALE: 1 in = 500 ft

SHEET 1 OF 2

REVISION NO.:

DATE:

NOTES:



# Sediment Basin 053

## Cell "B"

*Bear Run Mine*

*Permit S-256*

*25 Yr. 6 Hr. Storm Calculations*

Ken Paul

Peabody Midwest

Phone: 812-434-8586

Email: Kpaul@peabodyenergy.com


## *General Information*

### *Storm Information:*

Storm Type:	NRCS Type II
Design Storm:	25 yr - 6 hr
Rainfall Depth:	3.800 inches

### Structure Networking:

Type	Stru #	(flows into)	Stru #	Musk. K (hrs)	Musk. X	Description
Pond	#1	==>	#3	0.000	0.000	POND
Pond	#2	==>	#3	0.000	0.000	POND
Pond	#3	==>	End	0.000	0.000	SB 053 Cell "B"





### *Structure Summary:*

		Immediate Contributing Area (ac)	Total Contributing Area (ac)	Peak Discharge (cfs)	Total Runoff Volume (ac-ft)
A	#2 In			584.83	40.18
	Out	349.290	349.290	58.97	40.19
	#1 In			659.02	59.01
	Out	493.000	493.000	76.32	58.09
	#3 In			158.30	107.24
	Out	78.000	920.290	138.29	107.04

## Structure Detail:

### Structure #2 (Pond)

#### POND

Pond Inputs:

Initial Pool Elev:	516.00 ft
Initial Pool:	1773.85 ac-ft

#### Emergency Spillway

Spillway Elev	Crest Length (ft)	Left Sideslope	Right Sideslope	Bottom Width (ft)
516.00	20.00	3.00:1	3.00:1	20.00

Pond Results:

Peak Elevation:	516.67 ft
Dewater Time:	2.12 days

*Dewatering time is calculated from peak stage to lowest spillway*

#### Elevation-Capacity-Discharge Table

Elevation	Area (ac)	Capacity (ac-ft)	Discharge (cfs)	Dewater Time (hrs)
440.00	12.490	0.000	0.000	
442.00	12.972	25.461	0.000	
444.00	13.463	51.895	0.000	
446.00	13.963	79.320	0.000	
448.00	14.473	107.755	0.000	
450.00	14.991	137.218	0.000	
452.00	15.519	167.726	0.000	
454.00	16.055	199.299	0.000	
456.00	16.601	231.954	0.000	
458.00	17.156	265.710	0.000	
460.00	17.720	300.585	0.000	
462.00	18.232	336.536	0.000	
464.00	18.750	373.516	0.000	
466.00	19.276	411.541	0.000	
468.00	19.809	450.624	0.000	
470.00	20.349	490.781	0.000	
472.00	20.897	532.026	0.000	

Elevation	Area (ac)	Capacity (ac-ft)	Discharge (cfs)	Dewater Time (hrs)
474.00	21.452	574.374	0.000	
476.00	22.014	617.839	0.000	
478.00	22.584	662.435	0.000	
480.00	23.160	708.178	0.000	
482.00	23.718	755.054	0.000	
484.00	24.281	803.052	0.000	
486.00	24.852	852.184	0.000	
488.00	25.429	902.463	0.000	
490.00	26.012	953.903	0.000	
492.00	26.603	1,006.517	0.000	
494.00	27.200	1,060.318	0.000	
496.00	27.803	1,115.320	0.000	
498.00	28.414	1,171.536	0.000	
500.00	29.030	1,228.978	0.000	
502.00	30.233	1,288.237	0.000	
504.00	31.461	1,349.927	0.000	
506.00	32.713	1,414.097	0.000	
508.00	33.990	1,480.796	0.000	
510.00	35.291	1,550.072	0.000	
512.00	36.616	1,621.974	0.000	
514.00	37.966	1,696.552	0.000	
516.00	39.340	1,773.853	0.000	Spillway #1
516.67	40.414	1800.877	58.972	45.30 Peak Stage
518.00	41.637	1,854.820	176.689	
520.00	44.000	1,940.446	638.741	

*\*Designates time(s) to dewater have been extrapolated beyond the 50 hour hydrograph limit.*

Detailed Discharge Table

Elevation (ft)	Emergency Spillway (cfs)	Combined Total Discharge (cfs)
440.00	0.000	0.000
442.00	0.000	0.000
444.00	0.000	0.000
446.00	0.000	0.000
448.00	0.000	0.000
450.00	0.000	0.000
452.00	0.000	0.000
454.00	0.000	0.000

Elevation (ft)	Emergency Spillway (cfs)	Combined Total Discharge (cfs)
456.00	0.000	0.000
458.00	0.000	0.000
460.00	0.000	0.000
462.00	0.000	0.000
464.00	0.000	0.000
466.00	0.000	0.000
468.00	0.000	0.000
470.00	0.000	0.000
472.00	0.000	0.000
474.00	0.000	0.000
476.00	0.000	0.000
478.00	0.000	0.000
480.00	0.000	0.000
482.00	0.000	0.000
484.00	0.000	0.000
486.00	0.000	0.000
488.00	0.000	0.000
490.00	0.000	0.000
492.00	0.000	0.000
494.00	0.000	0.000
496.00	0.000	0.000
498.00	0.000	0.000
500.00	0.000	0.000
502.00	0.000	0.000
504.00	0.000	0.000
506.00	0.000	0.000
508.00	0.000	0.000
510.00	0.000	0.000
512.00	0.000	0.000
514.00	0.000	0.000
516.00	0.000	0.000
518.00	176.689	176.689
520.00	638.741	638.741

## Structure #1 (Pond)

### POND

Pond Inputs:

Initial Pool Elev:	520.00 ft
Initial Pool:	658.24 ac-ft

### Emergency Spillway

Spillway Elev	Crest Length (ft)	Left Sideslope	Right Sideslope	Bottom Width (ft)
520.00	20.00	3.00:1	3.00:1	12.00

### Pond Results:

Peak Elevation:	521.40 ft
Dewater Time:	0.66 days

*Dewatering time is calculated from peak stage to lowest spillway*

### Elevation-Capacity-Discharge Table

Elevation	Area (ac)	Capacity (ac-ft)	Discharge (cfs)	Dewater Time (hrs)
475.00	0.540	0.000	0.000	
477.00	1.737	2.164	0.000	
479.00	3.610	7.398	0.000	
480.00	4.800	11.589	0.000	
481.00	5.359	16.666	0.000	
483.00	6.568	28.572	0.000	
485.00	7.900	43.020	0.000	
487.00	8.755	59.668	0.000	
489.00	9.651	78.067	0.000	
491.00	10.592	98.304	0.000	
493.00	11.577	120.466	0.000	
495.00	12.603	144.639	0.000	
497.00	13.677	170.912	0.000	
499.00	14.792	199.374	0.000	
501.00	15.951	230.110	0.000	
503.00	17.155	263.210	0.000	
505.00	18.400	298.758	0.000	
507.00	19.784	336.934	0.000	
509.00	21.219	377.928	0.000	
511.00	22.703	421.841	0.000	
513.00	24.237	468.772	0.000	
515.00	25.821	518.822	0.000	
517.00	27.455	572.090	0.000	
519.00	29.139	628.676	0.000	
520.00	30.000	658.245	0.000	Spillway #1
521.00	30.579	688.534	31.357	11.69*
521.40	30.816	700.870	76.325	4.05 Peak Stage

Elevation	Area (ac)	Capacity (ac-ft)	Discharge (cfs)	Dewater Time (hrs)
523.00	31.753	750.862	258.549	
525.00	32.950	815.562	721.469	

*\*Designates time(s) to dewater have been extrapolated beyond the 50 hour hydrograph limit.*

### Detailed Discharge Table

Elevation (ft)	Emergency Spillway (cfs)	Combined Total Discharge (cfs)
475.00	0.000	0.000
477.00	0.000	0.000
479.00	0.000	0.000
480.00	0.000	0.000
481.00	0.000	0.000
483.00	0.000	0.000
485.00	0.000	0.000
487.00	0.000	0.000
489.00	0.000	0.000
491.00	0.000	0.000
493.00	0.000	0.000
495.00	0.000	0.000
497.00	0.000	0.000
499.00	0.000	0.000
501.00	0.000	0.000
503.00	0.000	0.000
505.00	0.000	0.000
507.00	0.000	0.000
509.00	0.000	0.000
511.00	0.000	0.000
513.00	0.000	0.000
515.00	0.000	0.000
517.00	0.000	0.000
519.00	0.000	0.000
520.00	0.000	0.000
521.00	31.357	31.357
523.00	258.549	258.549
525.00	721.469	721.469

Structure #3 (Pond)

SB 053 Cell "B"

Pond Inputs:

Initial Pool Elev:	509.00 ft
Initial Pool:	30.56 ac-ft

Emergency Spillway

Spillway Elev	Crest Length (ft)	Left Sideslope	Right Sideslope	Bottom Width (ft)
509.00	20.00	3.00:1	3.00:1	20.00

Pond Results:

Peak Elevation:	510.70 ft
Dewater Time:	0.33 days

*Dewatering time is calculated from peak stage to lowest spillway*

Elevation-Capacity-Discharge Table

Elevation	Area (ac)	Capacity (ac-ft)	Discharge (cfs)	Dewater Time (hrs)
500.00	0.220	0.000	0.000	
501.00	0.618	0.402	0.000	
502.00	1.211	1.300	0.000	
503.00	2.000	2.890	0.000	
504.00	2.709	5.235	0.000	
505.00	3.525	8.343	0.000	
506.00	4.449	12.321	0.000	
507.00	5.480	17.277	0.000	
508.00	6.621	23.319	0.000	
509.00	7.870	30.555	0.000	Spillway #1
510.00	8.203	38.591	49.679	1.96*
510.70	8.440	44.431	138.290	5.95 Peak Stage
511.00	8.542	46.962	176.689	
512.00	8.888	55.676	373.219	
513.00	9.241	64.740	638.741	
514.00	9.600	74.160	976.527	

*\*Designates time(s) to dewater have been extrapolated beyond the 50 hour hydrograph limit.*

Detailed Discharge Table

Elevation (ft)	Emergency Spillway (cfs)	Combined Total Discharge (cfs)
500.00	0.000	0.000
501.00	0.000	0.000
502.00	0.000	0.000
503.00	0.000	0.000
504.00	0.000	0.000
505.00	0.000	0.000
506.00	0.000	0.000
507.00	0.000	0.000
508.00	0.000	0.000
509.00	0.000	0.000
510.00	49.679	49.679
511.00	176.689	176.689
512.00	373.219	373.219
513.00	638.741	638.741
514.00	976.527	976.527



### *Subwatershed Hydrology Detail:*

Stru #	SWS #	SWS Area (ac)	Time of Conc (hrs)	Musk K (hrs)	Musk X	Curve Number	UHS	Peak Discharge (cfs)	Runoff Volume (ac-ft)
#2	1	349.290	0.202	0.000	0.000	78.000	M	584.83	40.183
$\Sigma$		349.290						584.83	40.183
#1	1	493.000	0.445	0.000	0.000	79.000	M	659.02	59.013
$\Sigma$		493.000						659.02	59.013
#3	1	78.000	0.438	0.000	0.000	78.000	M	100.42	8.964
$\Sigma$		920.290						158.30	107.238

### *Subwatershed Time of Concentration Details:*

Stru #	SWS #	Land Flow Condition	Slope (%)	Vert. Dist. (ft)	Horiz. Dist. (ft)	Velocity (fps)	Time (hrs)
#1	1	4. Cultivated, straight row	4.00	20.00	500.00	1.780	0.078
		8. Large gullies, diversions, and low flowing streams	1.85	100.00	5,405.00	4.080	0.367
#1	1	<b>Time of Concentration:</b>					<b>0.445</b>
#2	1	4. Cultivated, straight row	3.00	15.00	500.00	1.540	0.090
		8. Large gullies, diversions, and low flowing streams	2.71	53.90	1,989.00	4.930	0.112
#2	1	<b>Time of Concentration:</b>					<b>0.202</b>
#3	1	3. Short grass pasture	10.00	50.00	500.00	2.520	0.055
		8. Large gullies, diversions, and low flowing streams	0.28	6.00	2,170.00	1.570	0.383
#3	1	<b>Time of Concentration:</b>					<b>0.438</b>

# Sediment Basin Design Summary

05-Mar-11

## I. General Information

Mine: Bear Run Pit, Permit #256-4  
Basin: SB 053 cell "B"  
  
Basin Type: Incised  
Examination Exempt: Yes

## II. Design Parameters:

Design Storm Event : (10yr/24hr) 4.45  
Runoff Area (RA) (Treatment and Detention) 78.00  
Runoff Coefficient (RC) 0.52

## III. Runoff Calculation:

$$RV = RE \text{ (in / 24hr)} * 1\text{ft}/12 \text{ in} * \text{Runoff Area (ac)} * 43,560 \text{ sq ft /ac} * RC$$

where: RV = runoff volume (cubic ft/24hr)  
RE = runoff design event (inches/24hr)  
RC = runoff coefficient

$$RV = 651222 \text{ cubic ft /24hr} \quad 14.95 \text{ acre ft}$$

## IV. Treatment Volume Calculation:

Detention Time: DT 10 hours  
Sediment Volume: SV 531438 cubic ft  
Pit Pumpage Volume: PV 500 gpm

$$MCV = RV \text{ cf / 24hr} * 1\text{day}/24\text{hr} * DT \text{ hr} + PV \text{ gpm} \\ * 1440 \text{ min/day} * 1\text{day}/24\text{hr} * 0.1337 \text{ cf/gal} * DT \text{ hr} + SV \text{ cf}$$

$$\text{Minimum Compliance volume} = 842848 \text{ cubic ft} \quad 19.35 \text{ acre ft}$$

Basin Freeboard: 2.0 ft minimum at pool  
Basin Surface area: 7.87 acres 342817 sq ft  
Basin Minimum Average depth 2.46 ft

**Sediment Basin Design:**  
**Universal Soil Loss Calculation:**

05-Mar-11

Mine: Bear Run Pit, Permit #256-4

Basin: SB 053 cell "B"

**Soil Loss per Unit Area:**

$$A = R * K * LS * CP \quad A = 245.28 \text{ tons/acre}$$

where: A = Soil loss per acre (tons/acre)

R = Rainfall-Erosivity Factor 200

K = Soil Erodibility Factor 0.43

LS = Length Slope Factor 4.00

CP = Cropping Practice Factor 0.71

**LS Factor Calculation**

$$LS = (FSL/72.6)^m * ((430x^2 + 30x + 0.43) / 6.613) \quad 4.00$$

where: FSL = Field Slope Length 2670.00

x = Field Slope Ratio 0.0669

m = slope factor 0.5

slope < 3% m=0.3 , = 4% m=0.4, >5% m=0.5

**CP Weighted Factor Calculation**

Ground Cover Description	CP Value	Area (ac)	CP*ac
Active Disturbed area	0.90	60.00	54.00
Reclaimed or Undisturbed	0.09	18.00	1.62
		78.00	55.62
			0.71 Weighted CP

**Sediment Delivery Ratio:**

$$D = Da * Dv * Dc * Dp \quad D = 0.25$$

where: D = sediment delivery ratio 0.25

Da = area delivery ratio 0.50

Dv = Vegetation trapping factor 1.00

Dc = Channelization factor 0.50

Dp = pit deposition factor 1.00

**Sediment Yield From Design Watershed:**

$$Y = A * D \quad Y = 61.32 \text{ tons/acre}$$

where: Y = Watershed Sediment Yield (Tons / Acre)

A = Soil loss per area (Tons / Acre)

D = Sediment Delivery Ratio

Life of Basin 5.0 years

**Sediment Yield Conversion Ac ft / ac year:**

$$Y2 \text{ (ac ft / ac yr)} = (Y \text{ t/ac} * 2000 \text{ lb/t}) / (90 \text{ lb/cubic ft} * 43560 \text{ sq ft / ac})$$

$$Y2 = 0.03128 \text{ ac ft / ac yr}$$



**Sediment Storage Calculation:**

$$SL = RA * Y2 * YR * 43560 \quad \text{Design Sediment Storage} =$$

531438 cubic ft

# SB 053 Cell "B" Design Volume Summary


Surface Area 7.87 acres  
 Impounded volume: 0.0 ac ft  
 Design Treatment volume: 30.33 ac ft  
 Minimum Compliance Volume: 19.35 ac ft  
 Surplus Volume: 10.98 ac ft




HOR. 1" = 300'

Peabody Midwest Mining LLC	DATE: 3-3-2011	REVISION NO.: DATE:
Sediment Control Basin SB 053 Cell "B"	SCALE: 1 in = 300 ft	NOTES:
Bear Run Mine, Permit #256	SHEET 1 OF 2	

# Basin SB 053 Cell "B"




HZ 1 = 300 VT 1 = 30




HZ 1 = 300 VT 1 = 30

## Basin SB 053 Cell "B" Combination Spillway




509.0 elev. Inlet      Proposed Crest Control Section      509.0 elev. Outlet



Spillway Profile

NOT TO SCALE



3-16-11

Peabody Midwest Mining LLC		DATE: 3-3-2011	REVISION NO.:	DATE:
Sediment Control Basin SB 053 Cell "B" Cross-sections and Spillway Section Bear Run Mine, Permit #256-4		SCALE: As-Noted	NOTES:	
		SHEET 2 OF 2		